NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION NATIONAL OCEAN SERVICE

DESCRIPTIVE REPORT

Type of Survey ... Field Examination

Field No. ... PHP-5-2-95

Registry No. ... FE-419

LOCALITY

State ... Washington ...

General Locality ... Puget ... Sound ...

Sublocality ... East ... Waterway ...

1995

CHIEF OF PARTY


LT Richard A. Fletcher, NOAA ...

LIBRARY & ARCHIVES

APR 16 1996

FE419

1-72) NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION	
HYDROGRAPHIC TITLE SHEET	FE-419
INSTRUCTIONS - The Hydrographic Sheet should be accompanied by this form, filled in as completely as possible, when the sheet is forwarded to the Office.	
State Washington	
General locality Puget Sound	
LocalityEast Waterway	
Scale 1:5000 Date of s	survey <u>July 12, 1995</u>
Instructions dated Not Applicable Project	NoNot Applicable
Vessel SeaArk Launch 1102 (EDP #0652)	
Chief of party LT Richard A. Fletcher, NOAA	
Surveyed by LT R. A. Fletcher, LT(jg) E. W. Berkowit	
JULYEVEU DV	
Soundings taken by echo sounder, NXXX Kear, NAME Innerspace Mo	del 448
Soundings taken by <u>echo sounder</u> , Nank Keard, pare Innerspace Mo	del 448
Soundings taken by echo sounder, NXXXX KMAX, NAME Innerspace Moderation of the Control of the Co	del 448
Soundings taken by echo sounder, NXXXX Kend, NAME Innerspace Moderated Scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Verified by J. Stringham, B. Olmstead Auto	del 448
Soundings taken by echo sounder, NXXXX KMAX, NAME Innerspace Moderation of the Control of the Co	del 448
Soundings taken by echo sounder, NXXX NAM, NAME Innerspace Modern Graphic record scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Protracted by J. Stringham, B. Olmstead Auto Verification by by B. Olmstead	del 448
Soundings taken by echo sounder, NXXXX Kend, NAME Innerspace Moderation of the Control of the Co	omated plot by HP Design Jet 650C
Soundings taken by echo sounder, NXXXX Kend, NAME Innerspace Moderation of the Control of the Co	omated plot by HP Design Jet 650C
Soundings taken by echo sounder, NXXX KMX, NAME Innerspace Moderation of the scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Verified by J. Stringham, B. Olmstead Auto Verification by B. Olmstead Soundings in XXXXXXX feet at XMXXX MLLW	omated plot by HP Design Jet 650C
Soundings taken by echo sounder, Nank Keen, Nake Innerspace Moderate of Scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Verified by J. Stringham, B. Olmstead Auto Verification by B. Olmstead Soundings in XXXXXXX feet at XXXXX MLLW REMARKS: All times are UTC. Revisions and man	omated plot by HP Design Jet 650C rginal notes in black were All separates are filed with
Soundings taken by echo sounder, NXXXX KMAN, NAME Innerspace Moderated Scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Verified by J. Stringham, B. Olmstead Auto Evaluated by B. Olmstead Soundings in XXXXXXX feet at XXXXX MLLW REMARKS: All times are UTC. Revisions and management and during office processing.	omated plot by HP Design Jet 650C rginal notes in black were All separates are filed with
Graphic record scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Protracted by J. Stringham, B. Olmstead Protracted by B. Olmstead Soundings in XXXXXXX feet at XXXXX MLLW REMARKS: All times are UTC. Revisions and managemerated during office processing. the hydrographic data, as a result page.	omated plot by HP Design Jet 650C rginal notes in black were All separates are filed with
Graphic record scaled by LT G. T. Noll, LT J. Verlaque Graphic record checked by LT G. T. Noll, LT J. Verlaque Protracted by J. Stringham, B. Olmstead Protracted by B. Olmstead Soundings in XXXXXXX feet at XXXXX MLLW REMARKS: All times are UTC. Revisions and managemerated during office processing. the hydrographic data, as a result page.	omated plot by HP Design Jet 650C rginal notes in black were All separates are filed with rige numbering may be interrupted
Soundings taken by echo sounder, Nack Keevil, wakeInnerspace Moderaphic record scaled byLT G. T. Noll, LT J. Verlaque Graphic record checked by _LT G. T. Noll, LT J. Verlaque	omated plot by HP Design Jet 650C rginal notes in black were All separates are filed with rige numbering may be interrupted



Descriptive Report to Accompany Field Examination FE-419

Field Number PHP-5-2-95 Scale 1:5,000 1995

Pacific Hydrographic Party Chief of Party: LT Richard A. Fletcher

A. PROJECT

This Field Examination, registry number FE-419, was conducted to obtain modern data for the maintenance of existing nautical charts. The project responds to concerns expressed by the U.S. Navy which requested a reconnaissance survey, through contact with the Pacific Marine Center, of the East Waterway of Elliotte Bay and a positive resolution of a shoal along pier 37.

The area is frequented by deep-draft container ships. The main concern is the charted shoal along pier 37 where the aircraft carrier Kitty Hawk was assigned to berth during the 1995 Seafair activities.

PHP-5-2-9 $\rlap/\!\!\!/$ is the field number assigned to this survey.

B. AREA SURVEYED See Eval Rpt, Section B

The area surveyed is the East Waterway of Elliott Bay and the face of terminal 46, from latitude $47^{\circ}34'42"N$ to $47^{\circ}36'00"N$ and from longitude $122^{\circ}20'24"W$ to $122^{\circ}20'42"N$. Plotter sheet 1 was skewed to 270° with overall sheet limits measuring 20 cm by 70 cm. The inshore hydrographic limit for FE 7419 was the wharf faces. Depths ranged from 4.85 meters to 26.87 meters. (18-89 Feet)

FE-419 was surveyed at 1:5,000 scale standards, but at 1:10,000 scale position control requirements

All hydrographic data acquisition was conducted on July 12, 1995, (DN 193). A sound velocity cast was conducted on July 13, 1995 (DN 194). Data processing was completed at the Pacific Hydrographic Branch (PHB) July 14,1995 (DN 195).

C. SOUNDING VESSELS ✓

NOAA Launch 1102 (EDP No. 0652), a 21-foot SeaArk, was used for all hydrography, velocity casts, and developments. No changes to the standard vessel sounding configuration were necessary.

D. AUTOMATED DATA ACQUISITION AND PROCESSING $^{\checkmark}$

HYPACK for Windows version 5.2 was used for data acquisition throughout the project.

HYPCON program 2.16 was used for data conversion to HDAPS format and the raw data was submitted to the Pacific Hydrographic Branch for processing.

The following computer programs were used for supporting data:

<u>Program Name</u>	<u>Version</u>	<u>Date</u>
VELOCITY	2.10	1994
MONITOR	3.0	1995
GEOID93	1.00	1990

e. sonar equipment 🗸

No side scan sonar was used on this project. Concur

F. SOUNDING EQUIPMENT 🗸

The Innerspace Model 448 (IN-448) echosounder, s/n 239 was used on VN 0652.

The IN-448 had extreme difficulty tracking and correctly digitizing in the turbid water of the Duwamish River. Soundings were recorded in meters with a speed-of-sound through water of 1500 m/sec. Depths encountered in the survey area range from 4.8 meters to 26.8 meters.

No on-line calibration adjustments were required for the IN-448.

G. CORRECTIONS TO SOUNDINGS

Velocity of Sound

Corrections for the speed of sound through the water column were computed from data obtained with an Applied Microsystems Laboratories (AML) sound velocity profiler (S/N 03042). The VELOCITY program was used to determine the speed of sound correctors.

The following cast was used to determine the velocity correctors:

HDAPS Table	DN	Depth*	DN <u>Range</u>	Cast Position / <u>Latitude Longitude</u>
1	194	52.3	193	47°35'36"N 122°21'32"W

^{*}Extrapolated depth.

Separate IV contains copies of all velocity cast data and HDAPS Velocity Corrector Tables. Note that there were some depths deeper than the sound velocity cast, but not of navigational significance, offshore of the northern piers. Cest position falls outside the Survey limits.

The AML instrument was calibrated by Northwest Regional Calibration Center on April 15, 1994 (DN 105). A copy of this calibration report is included in Separate IV.

Static Draft 🗸

Static draft for VN 1102 was determined on April 12, 1994 (DN 102). First, the depth of the transducer face from a reference mark on the hull was measured. Next, with the launch in the water (fuel tanks half full and two personnel aboard) the depth from this reference mark to the launch's waterline was measured. Combining the two measurements, a static draft of 0.4 meters was calculated.

Dynamic Draft

Settlement and squat measurements for VN 1102 were conducted on April 5, 1994, (DN 095) in Guemes Channel, Washington. Field records are included in Separate IV.

Offset table 2 corresponds to VN 1102. Settlement and squat correctors were reapplied during office processing using the REAPPLY program in HDAPS.

Corrections to Echosoundings

Digitized soundings displayed on line were compared in real time with the analog trace to ensure reasonable agreement. As mentioned in section F, Sounding Equipment, digitizing the depths in the turbid water was difficult and significant manual editing of depths were necessary. All sounding edits were scanned and check-scanned at Pacific Hydrographic Branch during processing.

Tide Correctors / See Eval Rot, section 6

Tide correctors were not applied in the field but real tides were applied during office processing from the ElliottBay tide station data downloaded from headquarters. The operating tide station at

* Filed with the survey data

Seattle Washington (944-7130), is located less than 1 NM north of the East Waterway and serves as control for datum determination.

Straight line interpolation of the six-minute tide correctors (based on Mean Lower Low Water) was accomplished using the HDAPS program REAPPLY. Times and heights are direct on the datum station. No anomalous data are apparent, and the printout of the data is included in Appendix V.*

H. CONTROL STATIONS See Evel Rpt, Section H

The horizontal control datum for this project is North American Datum of 1983 (NAD 83). A copy of the HDAPS Control Station Table is included in Appendix III (List of Horizontal Control Stations). A separate Horizontal Control Report for OPR-N228-PHP, Eagle Harbor, was submitted to N/CG245 on July 25, 1995.

I. HYDROGRAPHIC POSITION CONTROL See Evel Rpt, Section I

Differential GPS (DGPS) was used for position control throughout this survey. Position accuracy requirements for a 1:10,000 scale survey were met as specified in the section 3.4 of the Field Procedures Manual.

The USCG DGPS beacon at Robinson Point was used throughout this project: Station plots outside the Survey limits.

Reference Station Latitude Longitude El. Ht
Robinson Point 47°23'18.953"N 122°22'26.745"W -6.031m

Reference sites were confirmed using program MONITOR per FPM section 3.4.6.3. Copies of scatter plots and outlier.sum files are included in Separate III $\overset{\bigstar}{\bullet}$ (Horizontal Position Control and Corrections to Position Data).

DGPS fixed point performance checks were obtained per FPM, Section 3.4.4.1 prior to and after data collection using a pile at the end of a pier at the Ferry Repair Facility in Eagle Harbor. The mark was positioned to Third Order, Class I standards (see Horizontal Control Report). All DGPS performance checks were successful; check forms are located in Separate III.

The following GPS equipment was used:

Equipment	Type of	Receiver	Antenna
Location	Receiver/Antenna	Serial No.	<u>Serial No.</u>
VN 1102	Ashtech (v.1E08D) CSI Beacon Rcvr.(MDL MBX1)	700417B1043	700378B0402
VN 1102		X-1212	M-2253

Offset and layback correctors for the GPS antenna are included in offset table 2.

J. SHORELINE See Enel Rpt, Section J.

No shoreline verification was conducted in the field, as no source was available.

K. CROSSLINES See EV2/ Rpt, Section K.

Two lines were run diagonally at 45° to the mainscheme hydrography. No comparison was conducted in the field.

L. JUNCTIONS 🗸

There are no junctions. Concur

M. COMPARISON WITH PRIOR SURVEYS See EU2/ Rpt, Section M.

No prior surveys were on hand for comparison.

N. ITEM INVESTIGATION REPORTS

There are no AWOIS items. Concur

O. COMPARISON WITH THE CHART See Evel Rot, section O.

PHP conducted online comparisons between the digitized soundings and chart 18450, 12th Edition, Jan 26, 1991 to ensure reasonable agreement. A more rigorous comparison will be performed by Pacific Hydrographic Branch, N/CS34 after application of smooth tides.

No indication of the charted shoal along pier 37 was found. Delete shoal charted at latitude 47°35'03"N Longitude 122°20'36"W and replace with depths from this survey. Concur Depths of the -41 feet were found in the vicinity of the charted 30 feet Sounding.

A bar was found centered at Latitude 47°35'08"N Longitude 122°20'40"W with a least depth of 47 feet. It appears this may be an area that was missed during the last dredging operations of the East Waterway. Concur Chart this area based on the present Survey information.

Danger to Navigation See Evil Rpt, Section O.

No dangers to navigation were found. Further review after smooth tides are applied may indicate dangerous depths within developments.

P. ADEQUACY OF SURVEY / See Evel Rpt, Section P.

This survey is complete and adequate to supersede all prior surveyed depths, and to update the depth contours in the immediate vicinity. Concur

Q. AIDS TO NAVIGATION See EUX Ret, Section Q.

All aids to navigation seaward of the 5-meter curve were positioned. All positions showed good agreement with the charted positions. An uncharted light was positioned at the northwest corner of the USCG pier 36. The light is privately maintained by the Port of Seattle. Mr. Jim Boyd of the Port of Seattle, (206)728-3135, was contacted to verify the position but he could not find a recorded position for the light. Although the light was only positioned using Hydrographic standards, DGPS, PHP recommends charting the light, see NF 76-40. See Edendum to Section Q dated 1/1/96 (attached).

R. STATISTICS

Description	<u>Ouantities</u>			
Total Positions (selected soundings) Total Detached Positions Total Nautical Miles Hydrography Square Nautical Miles Hydrography Velocity Casts Days of Production Bottom Samples	1483 4 20.2 0.12 1 1			
Tide Stations established	U			

s. miscellaneous ✓

Bottom samples were not acquired.

Q. AIDS TO NAVIGATION

Some doubt appears in this paragraph about the red light positioned on the NW corner of pier 36. The official name of the light was not shown in the DR or on NOAA FORM 76-40. I contacted Mr. Jim Boyd of the Port of Seattle (728-3135) and he confirmed the Descriptive Report. The Port does not maintain that light. He suggested I contact the Coast Guard Aids to Navigation Branch here in Seattle.

I contacted the Aids to Navigation/Waterways Management Branch phone number 220-7270 and spoke with a Lt. Matthew. I gave Lt. Matthew our position of the light and he searched for the light and finally confirmed the light was not an Aid to Navigation. He believes the light is a red pier light to help vessels in seeing the pier when mooring at 36. Lt. Matthew also, advised me that the two lights on Pier 34 were both discontinued on December 15, 1995 because of new construction.

The Light List Names of the two lights are:

Pier 34 North Dock Light LLNR 16865 Pier 34 South Dock Light LLNR 16870 These lights have been shown on the field examination as they were in existence at time of survey operations.



UNITED STATES DEPARTMENT OF COMMERCE National Oceanic and Atmospheric Administration

NATIONAL OCEAN SERVICE OFFICE OF COAST SURVEY Pacific Hydrographic Branch Seattle, Washington 98115-0070

February 20, 1996

Commander
Thirteenth Coast Guard District (OAN)
Federal Building, Room 3410
915 Second Avenue
Seattle, WA 98174-1067

Dear Sir:

Five dangers to navigation have been identified by Pacific Hydrographic Branch within the survey limits of field examination FE-419 (Pacific Hydrographic Party, July 12, 1995). These dangers affect the following charts:

Chart	Edition/Date	<u>Scale</u>	<u>Datum</u>
18450	13th Ed./Aug 22,	1992 1:10,000	NAD83
18449	15th Ed./Oct 29, 1	1994 1:25,000	NAD83

The attached information is provided for publication in the <u>Local Notice to Mariners</u>. A copy of chart 18450 showing the area in which the dangers exist is also attached.

Questions concerning this report should be directed to the Pacific Hydrographic Branch at (206) 526-6853.

Sincerely,

Kathryn Timmons Commander, NOAA Chief, Pacific Hydrographic Branch

Enclosures

cc: DMAHTC N/CS261 PMC

FIL	F	DV

CODE	SURNAME	DATE	CODE	SURNAME	DATE
N/CS341	Haines /	1209	6	AZOMIKA GA.	
N/CS341	Hill <i>Ol</i> f	Thok		, July noar	N.
N/CS34	Timmons K7	2/20/			Table 1
			·	4	F 61

Field Examination Registry Number:

Survey Title:

State:

Washington

Locality:

Puget Sound

Sublocality:

East Waterway of Elliott Bay

Project Number:

N/A

Survey Date: July 12, 1995

Features are reduced to Mean Lower Low Water using predicted tides.


Charts Affected:

18450 13th Edition/August 22, 1992 1:10,000 NAD83

18449 15th Edition/October 29, 1994 1:25,000 NAD83

<u>ITEM</u>	DANGER	<u>DEPTH</u>	LATITUDE (N)	LONGITUDE (W)	POSITION
A.	Shoal	43 feet	47°35'56.46"	122°20'24.64"	No. 100 /
В.	Shoal	47 feet	47°35'53.99"	122°20'26.33"	No. 177
C.	Shoal	39 feet	47°35'13.03"	122°20'37.51"	No. 863.01
D.	Shoal	38 feet	47°35'08.44"	122°20'37.43"	No. 527
E.	Shoal	42 feet	47°35'07.59"	122°20'38.92"	No. 991.01

Questions concerning this report should be directed to the Chief, Pacific Hydrographic Branch at (206) 526-6853.



NOAA FORM 76-40	40	U.S. DEPARTMENT OF COMMERCE	THENT OF COMMERCE	ORIGINATING ACTIVITY	TIVITY
Replaces C&GS Form 567.	m 567.	LANDWARKS FOR CHARTS		HYDROGRAPHIC PARTY GEODETIC PARTY PHOTO FIELD PARTY	± ≿
TO BE CHARTED		LOCALITY	DATE	COMPILATION ACTIVITY	۷۱۲۷
TO BE REVISED TO BE DELETED		Elliot Bay	9-19-95	COAST PILOT BRANCH	R REVIEW GRP.
The following objects	HAVE NAVE NOT	been inspected from seaward to determine their value as landmarks.	Š	(See reverse for responsible personnel)	ble personnel)
OPR PROJECT	JOB NUMBER	DATUM	MOLEACO TAKE GOVE THE	NOI FA CO	
	71-2-41	POSITION	(See instructions on reverse side)	on reverse side)	CHARTS
CHARTING	DESCRIPTION (Record reason for deletion of landmark or aid to navigation.	LATITUDE LONG!	OFFICE	FIELD	AFFECTED
a'	Fixed Red light	47 35 24.166 122 20 34.422		F-L-5-DGPS 18450	05481

\$ U. B.GPO:1975-0-665-040/1155

T. RECOMMENDATIONS

none

U. REFERRAL TO REPORTS

<u>Title</u> <u>Date</u>

Horizontal Control Report OPR-N228-PHP Eagle Harbor, WA

30 May, 1995

Approved and forwarded,

Richard A. Fletcher Lieutenant, NOAA Chief of Party

	9 7 1				-	11.7.6.1	FULL WALL WIRT	Station Name
- ype	Lat	Lon	H C	art	Freq	Ver Lode	HH/DD/YY	Station Name
	047 • 23 • 18 • 953	122:22:26.745	-19	0	0.0	0	62/28/95	Point Robinson
		000:00:00.000	0	0	0.0	0	03/01/92	
		000:00:00:000	O	0	0.0	0	03/01/92	
		000:00:00.000	Ŭ	0	0.0	0	93/01/92	
		000:00:00.000	0	0	0.0	0	03/01/92	
		000:00:00.000	0	0	0.0	0	03/01/92	
-	000:00:00.000	000:00:00.000	0	0	0.0	0	03/01/92	
	000:00:00.000	000:00:00.000	Û	Û	0.0	0	03/01/92	
	000:00:00.000	000:00:00.000	0	0	0.0	0	03/01/92	
	000:00:00.000	000:00:00.000	0	0	0.0	Û	03/01/92	
	000:00:00.000	000:00:00.000	0	0	0.0	0	03/01/92.	
	000:00:00.000	000:00:00.000	0	Û	0.0	0	03/01/92	
	000:00:00.000	000:00:00:000	0	0	0.0	0	03/01/92	
	000:00:00.000	000:00:00.000	0	0	0.0	Û	03/01/92	
	000:00:00.000	000:00:00:000	0	0	0.0	9	03/01/92	
	000:00:00.000	000:00:00.800	0	0	0.0	0	03/01/92	
	000:00:00.000	000:00:00.000	Ú	0	0.0	0	03/01/92	
	000:00:00.000	990:00:00.00	0	0	0.0	0	03/01/92	
	000:00:00.000	3 000: 00:00.000	0	0	0.0	Û	03/01/92	
	000:00:00.00	000:00:00.00	0	0	0.0	0	03/01/92	
	000:00:08.000	000:00:00.000	0	0	0.0	0	03/01/92	
	000:00:00.00	000:00:00.00	0	0	0.0	0	03/01/92	
	000:00:00.00	000:00:00:00	0	Q	0.0	0	03/01/92	
		000:00:00.00		0	0.0	0	03/01/92	
\		0 000:00:00.000		0	0.0	0	03/01/92	
		0 000:00:00.000		0	0.0	0	03/01/92	
		0 000:00:00.000		0	0.0	0	03/01/92	
		0 000:00:00.000		0	0.0	0	03/01/92	
		0 000:00:00.000		0	0.0	0	03/01/92	
	000:00:00.00	0 000:00:00.00) 0	Q	0.0	Ü	03/01/92	2

APPROVAL SHEET

for

SURVEY FE-419

Standard field surveying and processing procedures were followed in producing this survey in accordance with the Hydrographic Manual, Fourth Edition; the Hydrographic Survey Guidelines; and the Field Procedures Manual, as updated for 1995. The data were reviewed daily during acquisition and processing.

The digital data and supporting records have been reviewed by me, are considered complete and adequate for charting purposes, and are approved. All records are forwarded for final review and processing to N/CS34, Pacific Hydrographic Branch.

Approved and Forwarded,

DATE: September 19, 1995

Richard A. Fletcher Lieutenant, NOAA

Chief, Pacific Hydrographic Party

NOAA FORM 76-155 (11-72)	U.S. DEPARTMENT OF COMMERCE NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION						SURVEY NUMBER		
GEOGRAPHIC NAMES					FE-419				
Name on Survey	A 95	CHRIDAD PREVIOUS S	URVET US MAPS	MOLE NO LO NE OR LO	CAL WAPE	G RAM	MAP MENALLY DALLAS OF LAS	LIGHTLIS	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
EAST WATERWAY	Х	X							긔
ELLIOTT BAY	Х	Х							2
HARBOR ISLAND	Х	Х							3
WASHINGTON (title)	Х	Х							4
									5
							Ì		6
									7
									8
									9
									10
									11
									12
									13
									14
									15
									16
					-			1	17
				Approve	:ds		in this	1	18
								ì	19
				1/1	tio	2.4	21	·	20
				Clief G	eogra) het	/		21
				FEB	27	996			22
									23
				+					24
			1		· · · · · · · · ·				25

NOAA FORM 77	-27(H)		U.S. DEPARTMEN	NT OF COMMERCE	REGISTRY NUMBER	
(9-83)	HYDROGF	RAPHIC SURVEY	STATISTICS		FE-419	
RECORDS AC	COMPANYING SUI	RVEY: To be completed wh	nen survey is processed.			
RECORD DESCRIPTION AMOUNT			RECORD DESCRIPT		AMOUNT	
		VERLAYS: POS., ARC, EXCESS		0		
DESCRIPTIVE	DESCRIPTIVE REPORT 1 FIELD SHEE		FIELD SHEE	ETS AND OTHER OVERLAYS		0
DESCRIP- TION	DEPTH/POS RECORDS	HORIZ. CONT. RECORDS	SONAR- GRAMS	PRINTOUTS	ABSTRACTS/ SOURCE DOCUMENTS	
ACCORDION FILES						
ENVELOPES						
VOLUMES						
CAHIERS	1					
BOXES						
SHORELINE	DATA ///////////////////////////////////					
SHORELINE MA	APS (List): NA					
	METRIC MAPS (List):					
	HYDROGRAPHER (List):		*****			
SPECIAL REF		rt 18450 13th I				
NAUTICAL CI	HANTS (LISI). Cha		FFICE PROCESSING AC	CTIVITIES		
				artographer's report on the su	ırvey	
PROCESSING ACTIVITY			AMOUNTS			
		1.0110		VERIFICATION	EVALUATION	TOTALS
POSITIONS ON S	SHEET					1483
POSITIONS REVI	SED					
SOUNDINGS REV	VISED					
CONTROL STATI	ONS REVISED	···				
			VERIFICATION	TIME-HOURS EVALUATION	TOTALS	
PRE-PROCESSIN	NG EXAMINATION					
VERIFICATION O	F CONTROL					
VERIFICATION O	F POSITIONS					
VERIFICATION C						
	OF SOUNDINGS					
VERIFICATION O	OF SOUNDINGS					
VERIFICATION OF APPLICATION OF	DE SOUNDINGS DE JUNCTIONS					
VERIFICATION OF VERIFICATION OF SHORELINE APP	OF SOUNDINGS OF JUNCTIONS F PHOTOBATHYMETRY			17		17
VERIFICATION OF VERIFICATION OF APPLICATION OF SHORELINE APPLICATION OF COMPILATION OF SHORELINE APPLICATION OF SHORELINE	OF SOUNDINGS OF JUNCTIONS OF PHOTOBATHYMETRY PLICATION/VERIFICATION			17	3	17
VERIFICATION OF VERIFICATION OF APPLICATION OF SHORELINE APPLICATION OF COMPARISON W	OF SOUNDINGS OF JUNCTIONS OF PHOTOBATHYMETRY PLICATION/VERIFICATION OF SMOOTH SHEET	D CHARTS		17	3	
VERIFICATION OF VERIFICATION O	OF SOUNDINGS OF JUNCTIONS OF PHOTOBATHYMETRY PLICATION/VERIFICATION OF SMOOTH SHEET WITH PRIOR SURVEYS AN	D CHARTS ORDS		17	3	
VERIFICATION OF VERIFICATION O	OF SOUNDINGS OF JUNCTIONS OF PHOTOBATHYMETRY PLICATION/VERIFICATION OF SMOOTH SHEET WITH PRIOR SURVEYS AN E SIDE SCAN SONAR REC	D CHARTS ORDS		17	3	
VERIFICATION OF VERIFICATION O	OF SOUNDINGS OF JUNCTIONS OF PHOTOBATHYMETRY OF SMOOTH SHEET WITH PRIOR SURVEYS AN OF SIDE SCAN SONAR REC	D CHARTS ORDS		17		3

OTHER.				
'USE OTHER SIDE OF FORM FOR REMARKS TOTALS		17	14	31
Pre-processing Examination by LT Pamela Haines	Beginning Date 7/12/95	Ending Date 9/20	/95	
Verification of Field Data by J. Stringham, B. Olmstead		Time (Hours)	Ending Date 2/20	/96
Verification Check by B. Olmstead	Time (Hours) Ending Date 3/25/96		/96	
Evaluation and Analysis by B. Olmstead	Time (Hours) Ending Date 3 / 27 / 96		/96	
Inspection by D. Hill		Time (Hours) 2 Ending Date 3/29/96		/96

EVALUATION REPORT

FE-419

A. PROJECT

Project information is discussed in the hydrographer's report.

B. AREA SURVEYED

The purpose of this survey was to provide contemporary hydrographic data in the East Waterway, Elliott Bay, Washington, which supports considerable deep-draft traffic for the container and cargo handling facilities. Additional information and the survey limits are discussed in the hydrographer's report. Generally, depths range from 5.5 to 27.1 meters (18-89 FT). However, depths in the federal project area which supports the major shipping activity range from 36-60 feet.

C. SURVEY VESSELS

Survey vessel information is found in the hydrographer's report.

D. AUTOMATED DATA ACQUISITION AND PROCESSING

Survey data were processed using the same Hydrographic Data Acquisition/ Processing System (HDAPS) software used by the hydrographer, the Hydrographic Processing System (HPS) and AutoCad, Version 12.

At the time of the survey certification the format for transmission of digital data had not been formally approved. In the interim, digital data for this survey exists in the standard HPS format, which is a database format with the dbf extension. In addition, the sounding plot was created with a dbf (extension) and enhanced using the AutoCad system, are filed both in the AutoCad drawing format, dwg (extension); and in the more universally recognized graphics transfer format, dxf (extension). Copies of these files will be retained at PHB until transfer protocols are developed and improved.

The drawing files necessarily contain information which is not part of the HPS data set such as geographic name's text, line-type data, and minor symbolization. In addition, those soundings, deleted from the drawing for clarity purposes, remain unrevised in the HPS digital files to preserve the integrity of the original hydrographic data set. Cartographic codes used to describe the digital data are those authorized by Hydrographic Survey Guideline No. 75.

The field sheet parameters have been revised to center the hydrography on the office plot. The data is plotted using a Modified Transverse Mercator projection and are depicted on a single sheet.

E. SONAR EQUIPMENT

Sonar equipment information is found in the hydrographer's report.

F. SOUNDING EQUIPMENT

Sounding equipment is discussed in the hydrographer's report.

G. CORRECTIONS TO SOUNDINGS

The sounding data have been reduced to Mean Lower Low Water. The reducers include corrections for actual tide data, dynamic draft, and sound velocity. The reducers have been reviewed and are consistent with NOS specifications. Actual tide reduction is derived from the Puget Sound, Elliott Bay tide gage (944-7130).

H. CONTROL STATIONS

Sections H and I of the hydrographer's report contain adequate discussions of hroizontal control and hydrographic positioning.

The USCG DGPS beacon at Robinson Point was used for position control and is a published value based on NAD 83. The geographic positions of all survey data are also based on NAD 83. The field examination is annotated with an NAD 27 adjustment tick based on values determined with the NGS program NADCON.

Data based on NAD 27 may be referenced to this survey by applying the following corrections:

Latitude: -0.544 seconds (-16.791 meters) Longitude: 4.283 seconds (89.488 meters)

I. HYDROGRAPHIC POSITION CONTROL

Differential GPS (DGPS) was used to control this survey. A horizontal dilution of precision (HDOP) not to exceed 3.75 was computed for survey operations. The quality of several positions exceeds limits in terms of horizontal dilution (HDOP). These positions are isolated and occur randomly throughout the survey area. A review of the data, however, indicates that none of these fixes are used to position dangers to navigation. The features and or soundings located by these fixes are consistent with the surrounding information. These fixes are considered acceptable. System checks were performed by fixed point method to confirm the DGPS was operating properly.

J. SHORELINE

There were no contemporary shoreline manuscripts to support this survey. Although the hydrographer did not perform shoreline verification, a comparison with Chart 18450 13th ED August 1992 reveals that hydrography appears consistent with the charted shoreline.

K. CROSSLINES

Crosslines were run diagonally to the mainscheme hydrography. There was good agreement between the mainscheme and crossline hydrography.

L. JUNCTIONS

Junction information is discussed in the hydrographer's report.

M. COMPARISON WITH PRIOR SURVEYS

H-9169 (1970) 1:5,000

Survey H-9169 covers the entire area of the present survey. However, it appears that the only charted data which originates from this prior work are the soundings and piling in ruins located between Pier 27 and Berth 3 and the two dolphins located on the southern end of Terminal 37 and Pier 36. This is likely attributed to the fact that the East Waterway is a federal project area subject to periodic dredging and continual depth changes.

A comparison with the present survey generally reveals 1-3 foot differences throughout the East Waterway with no clear pattern as to shoaling or being consistently deeper. However, differences of 10-12 feet (deeper) are readily noticeable along many of the berthing areas and is directly attributable to contemporary dredging activities to support deeper draft vessels. The greatest shoreline changes have occurred between Berth 2 and Pier 32 and the southern end of Terminal 37. These shoreline changes are the result of fill to enlarge the container and cargo handling facilities.

With the exception of the following, Field Examination FE-419 is adequate to supersede the prior survey within the common area.

<u>Feature</u>	<u>Location</u>
6-foot depth	Pier 27/Berth 3
8-foot depth	Pier 27/Berth
14-foot depth	Pier 27/Berth 3
Piling in ruins	Pier 27/Berth 3
Dolphins (2)	Pier 36/ Terminal 37

N. ITEM INVESTIGATION REPORTS

There were no AWOIS Items assigned to this survey.

O. COMPARISON WITH CHART

Chart 18450, 13th edition, dated August 22, 1992; scale 1:50,000

a. Hydrography

Charted hydrography originates with the previously mentioned prior survey and miscellaneous sources. The prior suvey has been adequately addressed in section M and requires no further discussion. Charted miscellaneous soundings generally reflect the same differences with the present survey data as discussed in section M although charted pier face soundings currently reflect the deeper dredging that has taken place since 1970. Of note, the present survey found depths of 38-47 feet where the present chart shows 52-57 feet. This area is centered at latitude 47/35/09N, longitude 122/20/40W and extends approximately 125 meters west of Pier 33. This ridge-like feature rising above the bottom is likely an area missed during the last dredging operation.

FE-419 is adequate to supersede charted hydrography within the common area with the following exceptions:

<u>Feature</u>	Latitude(N)	Longitude(W)
Dol	47/35/29	122/20/34.5
Dol	47/35/23	122/20/35
Foul area	47/35/22.5	122/20/33
Pier ruins	47/35/20	122/20/35
Pier ruins	47/35/11	122/20/34
Pier ruins	47/35/04	122/20/36
Markers	47/35/00	122/20/35
Subm Cable Area	47/35/06	122/20/39

b. Dangers to Navigation

There were no dangers to navigation reported during survey operations. A total of five dangers to navigation were reported during office processing. A copy of this report is attached.

P. ADEQUACY OF SURVEY

Hydrography contained on FE-419 is adequate to:

- a. delineate the bottom configuration, determine least depths, and draw the required depth curves;
- b. reveal there are no significant discrepancies or anomalies requiring further investigation; and
- c. show the survey was properly controlled and soundings are correctly plotted.

The hydrographic records and reports received for processing are adequate and conform to the requirements of the Hydrographic Manual, 4th Edition, revised through Change No. 3, the Hydrographic Survey Guidelines, and the Field Procedures Manual, April 1994 Edition.

Q. AIDS TO NAVIGATION

There are three fixed aids to navigation located within the survey limits. These features were adequately located and serve their intended purpose. An additional light, Pier 36 Pier Light, is a privately maintained light red light marking the northwest corner of the pier and is currently not charted. This light was adequately located and serves its intended purpose.

There are no charted landmarks within the survey area.

R. STATISTICS

Statistics are itemized in the hydrographer's report.

S. MISCELLANEOUS

Miscellaneous information is discussed in the hydrographer's report.

T. RECOMMENDATIONS

This is a good field examination. No additional work is recommended.

U. REFERRAL TO REPORTS

Referral to reports is discussed in the hydrographer's report.

Bruce A. Olmstead Senior Cartographer

APPROVAL SHEET FE-419

Initial Approvals:

The completed survey has been inspected with regard to survey coverage, delineation of the depth curves, development of critical depths, cartographic symbolization, comparison with prior surveys and verification or disproval of charted data. The digital data have been completed and all revisions and processing have been entered in the magnetic tape record for this survey. The survey records and digital data comply with NOS requirements except where noted in the Evaluation Report. Final control, position and sounding printouts have been included with the survey records.

AlmoHul	Date: 4/5/96
Dennis Hill	
Chief, Cartographic Section	

I have reviewed the smooth sheet, accompanying data, and reports. This survey and accompanying digital data meet or exceed NOS requirements and standards for products in support of nautical charting except where noted in the Evaluation Report.

Kath Jumn ons Kathy Timmons	Date: 4/9/96	
Kathy Timmons Commander, NOAA Chief, Pacific Hydrographic Branch		

Date: 4 - 15 - 96

Final Approval

Approved:

Andrew A. Armstrong III
Captain, NOAA

Pacific Hydrographic Branch

Chief, Hydrographic Surveys Division

MARINE CHART BRANCH

RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. FE-415

INSTRUCTIONS

- A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.
- 1. Letter all information.
- 2. In "Remarks" column cross out words that do not apply.
- 3. Give reasons for deviations if any, from recommendations made under "Comparison with Charts" in the Review.

CHART	DATE	CARTOGRAPHER	REMARKS
8450	4/5/96	OHall	Full Part Before After Marine Center Approval Signed Via
<u> </u>	6/8/96	Ast	Drawing No. Full spolication of soundings from Smooth Sheet.
	4/-/	7	Sudge applied to chart Hum South.
18449	5.9.96	Maria Sitles	Full Part Before After Marine Center Approval Signed Via
	4		Drawing No. 77
18474	6 28 99	Pytublet	
16474	5/25/99	Rhubbeld	Full Research After Marine Center Approval Signed Via
	6/2/9	Dellarpine	Diadres No. 6
		, / 0	
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			E II Due Defens After Marine Contest Approved Signed Via
		-	Full Part Before After Marine Center Approval Signed Via
	<u> </u>		Drawing No.
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
· · · · · · · · · · · · · · · · · · ·			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			Full Part Before After Marine Center Approval Signed Via
			Drawing No.
			·